



- NOTES:
- 1. PRIMARY CABLES SHALL BE PLACED THRU THE LOWER OPENINGS.
 - 2. AFTER INSTALLATION OF CABLES AND GROUNDING, BACKFILL AND LEVEL THE SPACE, AS BELOW, TO THE PROPOSED FINISHED GRADE LEVEL.
 - 3.0 m SPACE IN FRONT OF FOUNDATION EDGE(S) ON OPERATION SIDE(S) OF EQUIPMENT.
 - 1.0 m IN FRONT OF FOUNDATION EDGES FOR OTHER SIDES.
 - 3. PLUG LIFTING HOLES WITH DUCT SEALING COMPOUND.
 - 4. SOME HIDDEN LINES ARE NOT SHOWN FOR CLARITY.
 - 5. SOME DUCTS ARE NOT SHOWN FOR CLARITY.
 - 6. EXPRESS CIRCUITS OR PRIMARY PHASES NOT REQUIRED IN FOUNDATION TO BE BYPASSED AS SHOWN IN DU-03-205-0500 & 0501.

PARTS LIST			
PART No.	MM No.	DESCRIPTION	QTY.
1	MM#	DISTRIBUTION EQUIPMENT FOUNDATION, CONCRETE, PRECAST	1
2	30009051	SEALANT, COMPOUND, DUCT SEALING	A/R
3	MM#	DUCT, DB2	A/R
MM# = REFER TO SECTION 16 ONLY A/R = AS REQUIRED			

ALL DIMENSIONS IN MILLIMETRES
UNLESS OTHERWISE STATED

01	SEP 2018	GENERAL UPDATES. CHANGED TO NEW DWG. & NUMBERING FORMAT. FOR PREVIOUS REVISIONS REFER TO DU-03-210.1-R0.	S0	PC	AS	PS
Rev No.	Date	Revision Particulars	dwn	ckd	des	app

Drawn By: L.S.	Checked By:	Designed By:	Design Approved By:
Scale: N.T.S.	Date: (yyyy/mm/dd) 2013/11/07	Pole ID:	



© Copyright Hydro One Networks Inc. All rights reserved. This drawing may not be reproduced or copied, in whole or in part, in any printed, mechanical, electronic, film, or other distribution and storage media or used in any information storage or retrieval system outside of Hydro One Networks Inc., without the written consent of Hydro One Networks Inc.
Information contained in this drawing is considered to be confidential. Recipients shall only use the drawing for its intended purpose and shall take necessary measures to prevent disclosure or transmittal to outside parties.

Title:
ALL-IN-DUCT
EQUIPMENT FOUNDATION INSTALLATION

Drawing No. DU-03-210.1-0500	Rev. No. 01
---------------------------------	----------------

TITLE BLOCK REV 02 – AUGUST 2014